


B 0.3

Engine, Installation, Accessories

Group	Number	Version
B 0.3	smc-07-87 vwm-07-07	01

Fuel system deaeration of the TDI 225-6 / 265-6 engines



1. Pull-off the plug of the pressure control valve
2. Let the starter turn for approx 30 seconds
3. Stop procedure for approx. 20 seconds
4. Repeat items 2 and 3 two times
5. Refit the plug of the pressure control valve and start the engine